BRUHATH BANGALORE MAHANAGARA PALIKE
PERCENTAGE TENDER SCHEDULE-B

D.T.S. COPY

'ssued to Sri

TEND NO:
ITEM NO:
Orginal/Duplicate

NAME OF WORK: Construction of BS Slab Drain & Culverts at Medarahalli, in Ward No-12, In Shettyhalli Sub-Division.

Sl. No	Quantity	Description of work	Unit	Tender Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	197.56	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications.	Cum	129.60	Rupees One Hundred Twenty Nine and Sixty Paise Only
2	482.40	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 cms thick	Cum	304.56	Rupees Three Hundred Four and Fifty Six Paise Only
3	8.28	Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	3349.08	Rupees Three Thousand Three Hundred Forty Nine and Eight Paise Only
4	25.92	Providing and laying in position plain cement concrete of mix 1:2:4 using 20mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	4388.04	Rupees Four Thousand Three Hundred Eighty Eight and Four Paise Only
5	12.10	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1:5:3) for raft foundation, column footing, main and secondary beams.	Cum	4491.72	Rupees Four Thousand Four Hundred Ninety One and Seventy Two Paise Only

D.T.S. is approved

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bangalore-73

Executive Engineer
Dasarahalli Division
B.B.M.P

Signature of the Contractor

6	14.26	providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Q	5204.52	Rupees Five Thousand Two Hundred Four and Fifty Two Paise Only
7	86.40	Providing and removing centering, shuttering, strutting, propping etc., for edges o slabs and breaks in floor, cills, plinth including cost of all materials, labour complete as per specification.	Cum	501.12	Rupees Five Hundred One and Twelve Paise Only
8	194.45	Conveying the excavaed earth to a distance of 2kms with all lead & lifts including loading & unloading charges etc., complete.	Cum	72.71	Rupees Seventy Two and Seventy Paise Only

D.T.S. is approved

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bangalore-73

Signature of the Contractor

Executive Engineer
Dasarahalli Division
B.B.M.P